

Ron's Express Carwash
& Oil Change

Seldom Seen Rd

Customer to:
 -Trench Approx 540FT, 36" Below Final grade, and
 Install 2 Runs of 3" Schedule 40 Conduit.
 -Stub end Near (North Side of) Pole 8" Away and Stub
 Transformer end. (Sweeping 90's).
 -Install Meter Base Per AEP Spec
 -Private Wire From Transformer to Meter.

Parking Lot
 Meter Location:
 NEW/UG/COMM/SVC
 400AMP 120/240V 1P 3W
 1836111791556
 IN 25KvA/ 120/240V
 DS2217

1836491791449
 EX Pole 45'5"
 IN 19.9Kv/A 1P Riser
 IN 3" Schedule 40 Conduit
 DS2301

(328,834)

(413,642)

(491,449)

Ball Field

Ball Field

Sanitation Easement

IN 1/0 AL URD

170'

175'

155'

20'

20'



Powered by AEP

| | | | |
|--|----------------------|------------------------|---------------------|
| JOB NAME: IN 19.9Kv 1P Riser, IN Approx 540FT 1/0 AL URD & Pad MT 25KvA 120/240V | | | NON-DESIGN ORDERS |
| LOCATION: 3242 SELDOM SEEN RD | | | OWR/OPS:103928490 |
| CITY: POWELL | DESIGN ORDERS | | JUP: |
| TWP: Liberty | OH: 70971027 | W/O: DOP0297527 | JUP: |
| COUNTY: Delaware | UG: | W/O: | JUP: |
| | AREA: 040 - Delaware | JUP: | OWR/OPS: |
| | STATION: SAWMILL F31 | TECH/ENG: Jamie Walker | QUAD: DEL |
| | CIRCUIT: 33 | CONTACT: 740-368-7155 | MAP: |
| | VOLTAGE: 19.9Kv | DATE: October 24, 2018 | SCALE: 1:80 |
| | | | SHEET: Sheet 1 of 1 |