

Ron's Express Carwash
& Oil Change

Seldom Seen Rd

Customer to:
 -Trench Approx 540FT, 36" Below Final grade, and
 Install 2 Runs of 3" Shchedule 40 Conduit.
 -Stub end Near (North Side of) Pole 8" Away and Stub
 Transformer end. (Sweeping 90's).
 -Install Meter Base Per AEP Spec
 -Private Wire From Transformer to Meter.

Parking Lot
 Meter Location:
 NEW/UG/COMM/SVC
 400AMP 120/240V 1P 3W
 1836111791556
 IN 25KVa/ 120/240V
 DS2217

1836491791449
 EX Pole 45'5"
 IN 19.9Kv/A 1P Riser
 IN 3" Schedule 40 Conduit
 DS2301

(328,834)

(413,642)

(491,449)

IN 1/0 AL URD

170'

175'

155'

20'

20'

Ball Field

Ball Field

Maint Building

Sanitation Easement



Powered by AEP

JOB NAME: IN 19.9Kv 1P Riser, IN Approx 540FT 1/0 AL URD & Pad MT 25KVa 120/240V

LOCATION: 3242 SELDOM SEEN RD

NON-DESIGN ORDERS

OWR/OPS:103928490

CITY: POWELL

DESIGN ORDERS

JUP:

OWR/OPS:

TWP: Liberty

OH: 70971027

W/O: DOP0297527

JUP:

OWR/OPS:

COUNTY: Delaware

UG:

W/O:

JUP:

OWR/OPS:

AREA: 040 - Delaware

JUP:

QUAD: DEL

STATION: SAWMILL F31

TECH/ENG: Jamie Walker

MAP:

CIRCUIT: 33

CONTACT: 740-368-7155

SCALE: 1:80

VOLTAGE: 19.9Kv

DATE: October 24, 2018

SHEET: Sheet 1 of 1

